



MARDEN NEIGHBOURHOOD PLAN 2017 - 2031

DRAFT FOR REGULATION 16





300 Years Ago

Traditional 'Hundred' map showing the main roads, rivers, woodlands and settlements in the Marden area East of the River Teise. Accuracy is somewhat variable, but still a useful historical record.

(Reproduced with kind permission of the Marden Society History Group)



200 Years Ago

The first Ordnance Survey map produced by Captain W. Mudge in 1801. This map shows the main geographical features with unprecedented levels of accuracy although field boundaries are sketched on diagrammatically.


(Reproduced with kind permission of Dennis Morris Esq)



100 Years Ago

2nd Edition Ordnance Survey map (1898) showing the main line railway and station - probably the most important factors in the village's development. New Victorian housing can be seen as 'ribbon development' along roads. Most place names have modern spellings and 100 ft contours are shown.

(Reproduced with kind permission of the Marden Society History Group)



Present Day

The Marden area today in the familiar modern Ordnance Survey style. The main change over the 20th century is the significant increase in the built up area in the village centre. Also visible is the HV overhead power line on the western side of the parish.

(Reproduced with kind permission of Ordnance Survey. © Crown copyright NC101/27347)



Cllr Kate Tippen
Chairman of Marden Parish Council

As Chairman of Marden Parish Council I am delighted to introduce this important document. As a long-time resident I am deeply committed to ensuring the ongoing economic and social wellbeing of the whole community. This document is a vital planning document that will help to shape the future development of our parish, so I encourage all of you to take the time to read what will be directly influencing your future.

My sincere thanks go to all those dedicated volunteers who have created this plan, to those Parish Councillors and members of the Steering Group who have given up so much of their time and offered their services with such good will. To all those residents who have taken the trouble to attend the open days and other community events, and to you who are now reading this valuable document.

A handwritten signature in black ink, appearing to read 'Kate Tippen'.

Kate Tippen



Cllr Andrew Turner
Chairman of Marden Neighbourhood Plan Steering Group

I was born and bred in Marden. I am passionate about my village and have welcomed the opportunity to be Chairman of the Steering Group which has co-ordinated the Marden Neighbourhood Plan on behalf of the parish.

I too offer my heartfelt thanks to all who have contributed to the production of this document and trust it will prove a vital tool to help local residents and businesses have their say in the planning decisions that will affect their future.

A handwritten signature in black ink, appearing to read 'Andy Turner'.

Andy Turner

MARDEN NEIGHBOURHOOD PLAN CONTENTS

- 1** Foreword
- 2** Contents
- 3** Introduction
- 9** Natural Environment
- 19** Built Environment
- 26** Amenities
- 32** Infrastructure
- 40** Economy
- 44** The Future?
- 46** Spatial Application of Policies
- 47** Annex 1 - Planning Policies and Future Action Plan
(including Marden Conservation Area)
Appendix 1
List of Further Actions and Owners
- 50** Annex 2 - Flood Plain Map
- 51** Annex 3 - Ancient Woodland and SSSIs Map
- 52** Annex 4 - Listed Buildings
- 57** Annex 5 - Acknowledgements

Introduction

Background



The planning system is always changing. Legislation has been introduced which is designed to give people a greater say in local decision-making. The Localism Act, which came into effect in November 2011, was designed to give greater powers to local councils, parishes and neighbourhoods – to empower local people to help them shape the growth of their communities in a sustainable way. A further major change in planning legislation introduced by the Government in 2012 was the National Planning Policy Framework (NPPF). This was intended to streamline the planning process and is now the key planning document in writing local plans and making planning decisions. The NPPF was updated in 2018 and 2019.

We hear a lot about sustainable development. What it means in this plan is development that allows us to develop but without harming the social, economic or environmental aspects of the village and wider parish for the future.

Marden parish, being located in the South East of England, faces great pressures for development. We need houses, we need jobs and we need adequate infrastructure and services to support them (including schools, health provision and transport networks).

In May 2011 public meetings were held to ask local people to get involved: to gather together the views of local residents and businesses to create a forward-looking plan. This plan has been achieved through the hard work of the Steering Group and all those who have become involved subsequently. The plan covers the whole of Marden Parish, which was designated a neighbourhood area on 14th January 2013 and covers a period to 2031.

The plan has been created by the people of Marden and could not exist without the support of the Parish Council and all those who have contributed. This document will be vital in safeguarding Marden's future as a thriving, sustainable community.



A Vision for Marden

“The overriding theme discussed by residents at all the open days and consultation events has been the Marden spirit – the feeling of community. This cannot be overstated and underpins all the Marden Neighbourhood Plan policies. It is the impetus for all those involved in the preparation of the document.”


Andy Turner, Chairman of the Marden Neighbourhood Plan Steering Group, 2014.

This plan is designed to ensure that Marden will continue to be a thriving parish, to maintain its individual character, heritage and community spirit. The plan aims to balance the existing and future needs of residents and businesses to fulfil Marden’s function as a Rural Service Centre, by managing the expansion of housing provision, employment, education and recreation opportunities, whilst retaining and enhancing the natural beauty and biodiversity of the surrounding rural area.



All about Marden

The rural village of Marden is in the middle of Kent, set in the heart of the Kentish Weald. It is likely that there has been a settlement here since the Bronze Age. However, not until the Romans left and the Jutes divided up the forest of the Weald of Kent did Marden get its name: 'Meredenne', a place where herdsmen from the North Kent coast brought their pigs in the autumn to fatten up on acorns and beech mast. By 1085 this clearing in the forest had a church (probably wooden) mentioned in the Domesday Monachorum. By the end of the 12th century the church was rebuilt in stone and in the 13th century the village was given to Queen Eleanor, with the right to hold a weekly market and annual fair.





Marden developed as a farming village, which led to many associated trades and businesses. For hundreds of years, timber, hops, corn and fruit were the mainstay of the village. Many of the buildings that were used for these activities survive and contribute to the character of the Marden we see today.

In 1842, a railway station was opened at Marden on the new South Eastern Railway Company line from London to Dover. This led to new markets for Marden's produce and the fruit and hop farms flourished. This period of prosperity is also associated with the annual influx of migrant hop and fruit pickers – so much part of the history of the village. The 2011 census showed a population in the parish of 3,724.



This rail link is still vital – it remains an important service for the village, with good access to London, Dover and continental Europe beyond. The railway has played, and still plays, a major part in the continuing growth of the village. The arrow straight line of the railway, running west to east, bisects Marden separating the majority of the housing to the south, and most of the industry to the north.



The parish of Marden is traversed by a network of narrow, unclassified lanes. For most residents the 'main road' is the B2079, from Goudhurst northwards towards Maidstone, to the east of the rivers Teise and Lesser Teise. This road keeps close to the 80ft (24m) contour along its route through the parish, apparently since it was first picked out by travellers on foot and then by horse and cart, to skirt the river floodplain. Through the village the B2079 is known as West End, Church Hill and then as the High Street. There are no other B roads but the A229 crosses the northern end of the parish for about one and a half miles, just south of the River Beult and its floodplain.



The parish is largely founded on low lying impermeable Wealden clay. The rivers Beult and Lesser Teise form the parish boundaries to the north and west. The water table is generally high and therefore water plays an important part in the landscape, with its many inter-linked ditches, ponds and streams. This functional drainage network is also essential in managing the risk of flooding to land and properties.



Although virtually all of the ancient Wealden forest has gone, trees still form an integral part of the Marden landscape. Remnant ancient woodland and replanted woodland are features of the southern area. Modern orchard farming has seen a change from the large, spreading fruit trees to the dwarf root stocks used today, but often still protected by tall windbreak hedges. The remaining farmland is given over to arable crops and livestock, although the parish is now also home to less traditional crops such as vines.

As we all know, farming practices have changed, but many features remain in the landscape, such as tall boundary hedges and oast houses, and these contribute to Marden's distinctive Wealden character.

Community-based plans - what are they and what are they for?

“Government is too big and too important to be left to the politicians”.

Chester Bowles
(US Politician 1901-1986)

Why does Marden need a community-based plan?

Plans written by local people are nothing new. Successive governments have supported the idea of local people getting together and producing documents that show how they want their community to develop. Previous parish or community plans and village design statements showed how local communities saw themselves and how they wanted to develop.

Marden already has two important documents written by local people:

Marden Design Statement 2001

This document, a village design statement, went further than merely looking at design, and was written in order to influence Maidstone Borough Council (MBC) and anyone wishing to develop land in the parish. It was adopted as Supplementary Planning Guidance which meant it became a material planning consideration when determining planning applications in Marden. However, following changes in planning legislation, the design statement no longer carries the legal weight it once did.

Marden Community Plan 2007

The community plan was produced in 2007, and this identified the opportunities and weaknesses facing the parish. It concentrated on the actions that could be taken to improve community facilities. The plan achieved its initial goals, but a number of actions are still ongoing.

The concept of community plans evolved into neighbourhood plans which now have a formal place in the planning system as part of the government's 'localism agenda'. Neighbourhood Plans contain spatial policies which will help to shape the future of the Neighbourhood Plan area. In order for these plans to work it is essential they reflect the views of the wider community.

Why does Marden need a Neighbourhood Plan?

There is constant pressure for growth in the South East of England. This means there is a constant pressure on Marden – a high demand for new housing and other types of development. Decisions about 'what sort of development is allowed to go where' are made through the planning system, in accordance with MBC's development plan with the National Planning Policy Framework (NPPF) as a material consideration.

MBC was in the process of producing a new local plan for many years to replace the Maidstone Borough Wide Local Plan 2000, but unfortunately it was delayed many times. This Neighbourhood Plan has been developed in parallel with the MBC Local Plan to ensure conformity. The MBC Local Plan was adopted on 25th October 2017. The Kent Minerals Waste Local Plan 2013-20 (2016), which identifies minerals safeguarding areas, also forms part of the development plan covering Marden.

MBC has identified Marden as one of the five Rural Service Centres in the borough. This is because Marden has employment opportunities, good community facilities and frequent rail connections to London. Consequently, Marden has been identified as a village that would benefit from increased housing and development likely to generate more employment opportunities.

What is the role of Marden Parish Council?

Marden Parish Council is the 'qualifying body' for producing the Marden Neighbourhood Plan. The Parish Council has the power to initiate the process and produce the final document.

What are the objectives of the Marden Neighbourhood Plan?

The Marden Neighbourhood Plan aims to ensure that all future development carried out in Marden parish is sustainable and will not result in unacceptable harm to the form and function of the village and the wider parish.

The plan provides local policies on issues of specific importance to the community of Marden which have the objective of retaining, and wherever possible, enhancing the rural Wealden character and distinctiveness of the whole parish. A number of further actions are also identified together with the parties best placed to implement them.

It also contains background information and guidance to help developers and planners make good decisions that will benefit the community both now and in the future.



Natural Environment

The rural parish of Marden lies in the Low Weald of Kent at an average height of 18 metres (sixty feet) above sea level. The northern boundary follows the sinuous River Beult flowing from east to west to join the River Medway at Yalding. The western parish boundary follows the meanders of the Lesser Teise river, which drains north to join the Beult, west of the hamlet of Chainhurst.



The short southern boundary is contained by the rising land of the High Weald escarpment, the highest point being about 60 metres (190 feet). The remaining boundary is relatively ill-defined on the ground, running south west/north east through ancient re-planted deciduous woodland, over a low hill at Marden Thorn, and across arable and grass fields to the River Beult. The church and older core of Marden village lies centrally within the parish, adjacent to the railway, at the hub of the road network. The parish covers some 3100 hectares (7600 acres), extending 8 km (five miles) from south to north.



The NPPF requires the planning system to protect and enhance valued landscapes and minimise impact on biodiversity. It recognises that development should contribute to and enhance the natural and local environment, and areas of tranquillity that are prized for their recreational and amenity value. Marden Neighbourhood Plan has enthusiastically embraced the aims of the NPPF to conserve and enhance the natural environment by:



- Protecting and enhancing valued landscapes, sites of biodiversity value and soils;
- Recognising the intrinsic character and beauty of the countryside and the wider benefits from natural capital and ecosystem services;
- Providing net gains for biodiversity;
- Establishing coherent ecological networks;
- Helping to improve local environmental conditions;
- Safeguarding components of local wildlife-rich habitats;
- Promoting priority habitats and species;
- Protecting irreplaceable habitats (such as ancient woodland and ancient or veteran trees).

However, it is essential that specific issues of local importance are fully taken into account in the planning process, and these are addressed in this Plan.



The NPPF defines green infrastructure as a network of multi-functional green spaces, urban and rural, which is capable of delivering a wider range of environmental and quality of life benefits for local communities with blue infrastructure as a network of water features in the landscape. MBC has a Green and Blue Infrastructure Strategy which recognises the contribution that green space and the water environment can make. The importance of such areas are reflected where relevant in the policies within this Plan.

Surface Water Management



The Rivers Beult and Lesser Teise both have functional floodplains, the main expanse of flooding being between Marden village and Chainhurst to the east, an area notable for the network of drains. During extreme rainfall events Chainhurst can be surrounded as an island with flows in the ditches connecting the two floodplains. The west side of the village, including the industrial site to the north, also experiences fluvial (river) flooding from the Lesser Teise and its tributaries. The situation is aggravated by highway flooding, surface water flooding and sewerage system failures.

“The main cause of past flood incidents (in Marden) has been heavy rainfall causing surface water flooding due to inadequate drainage systems. Any increases in surface water run-off in Marden, due to future developments or increase in rainfall due to climate change will have implications on flood risk downstream. The development of further properties (in Marden) should be used as an opportunity to assess and improve the current surface water drainage system. It is also essential that maintenance of existing and new drainage systems is carried out to ensure flooding caused by blockages is reduced; this falls under the responsibility of Southern Water and the owners of new developments.” (MBC Strategic Flood Risk Assessment 2008).

Kent County Council's (KCC) Marden Surface Water Management Plan partnership has developed a robust understanding of local flood risks, including the up-dating of flood records with recent events and preparation of an integrated catchment model for Marden, designed to assist the understanding of flood mechanisms and pathways, determine areas at risk of flooding and identify potential mitigation options. An objective of the study was to identify opportunities to deliver flood risk management benefits through local planning documents, including the Marden Neighbourhood Plan.

“The risk of surface water flooding in new development areas can be greatly reduced by the consideration of drainage in the planning process, and particularly by the incorporation of Sustainable Urban Drainage Systems (SuDs) into the design of new developments.” (MBC Water Cycle Study 2010)

Successful drainage schemes for new developments will be based on the provision of open channel surface water drainage, mimicking nature and the existing local features, rather than using underground pipes and storage systems. Where new drainage networks are specifically required they should incorporate and connect to existing ditches and streams as an integral part of the local environment.

Surface water features also create new habitat, encourage biodiversity and amenity use, in accordance with MBC Green and Blue Infrastructure aspirations. Edges or kerbs of impermeable materials such as paving should be flush with proposed soft landscape areas to allow water to drain directly, provided that there will be no risk of pollution from oil leaks etc., and that adequate arrangements are made for extreme rainfall events. This results in a more attractive setting especially for residential areas. All schemes will be expected to adopt best current industry practice for the site-specific conditions, including effective management and maintenance to meet all design objectives.

A written statement by the Secretary of State for the Department of Community and Local Government (Dec 2014) requires the planning system to be used to ensure that there are clear arrangements in place for ongoing maintenance of the sustainable drainage infrastructure for new developments.

POLICY NE1 – SURFACE WATER MANAGEMENT

Support will be given to development proposals that include appropriate sustainable surface water control systems designed to deliver efficient, clean water handling as well as wildlife and amenity benefits. Schemes must be accompanied by a detailed management plan confirming operating responsibilities to ensure the permanent management and maintenance of all elements of the schemes to maximise local benefits.



Further action required

- ▶ All partners to take forward the recommendations of KCC's Marden Surface Water Management Plan 2017, and revisions.
- ▶ Environment Agency to confirm whether all or part of Marden should be designated a Critical Drainage Area.
- ▶ All land owners with riparian responsibilities to ensure existing ditches are fit for purpose and maintained as such.

Water Quality



The EU Water Framework Directive required all inland waters to have 'good' chemical and ecological status by 2015, or where necessary by later dates. The yearly status of the parish boundary rivers has been assessed by the Environment Agency and objectives set, based on current conditions and anticipated river basin activities. The ecological status of the Beult is currently moderate, having improved from poor in 2014 to meet the 2015 objective. The ecological status of the Lesser Teise is similarly moderate, with the objective of achieving good by 2027. The equivalent status for chemical quality is good for both rivers, meeting their 2015 objectives. Marden Parish Council is represented on the Catchment Improvement Groups for the Beult and for the Teise.

In the Kent Biodiversity Strategy (Kent Nature Partnership 2015) both rivers are included in the Biodiversity Opportunity Area of the Medway and Low Weald Wetlands and Grasslands*. A potential relevant target is to "Pursue opportunities for creation of wider river floodplains with riparian corridors (river banks) around natural drainage channels" as part of the flood alleviation schemes and new development drainage initiatives.

It may also be possible to contribute to the target 'Pursue opportunities to create new species-rich neutral grassland, particularly close to the Marden Meadows Site of Special Scientific Interest....' The whole parish is a target area in the Natural England Sensitive Catchments programme for the rivers Beult, Teise and Lesser Teise, addressing sustainable agricultural practices to control diffuse pollution and soil erosion, amongst other issues.

**Maidstone Biodiversity Opportunity Areas are also incorporated into the Maidstone Landscape Character Assessment (Appendix D) 2012, as amended 2013*



Surface water in the parish generally drains either west to the Lesser Teise or north to the river Beult. For historic reasons, wastewater is pumped from north to south through the village to a treatment plant south of the parish in Horsmonden, from where the treated effluent is discharged to the Teise/ Lesser Teise drainage system, to flow north again. From the above summary of the complex water quality issues in Marden parish, it will be obvious how vulnerable the current status is to development on former agricultural land.

As noted in the preceding Surface Water Management section, the efficient operation of surface water drainage systems which keep water on the surface can be readily checked and easily maintained. These systems will help to meet the essential requirement to ensure there is no additional contamination load from new development in the parish. Maintenance of these drainage networks and the surrounding landscape will generate materials such as leaves and grit as well as grass cuttings and site layouts should incorporate appropriate spaces for their storage, treatment (composting) and subsequent re-use.

POLICY NE2 – WATER QUALITY

Development proposals that seek to protect the water quality downstream by strict controls on the potential release of contaminants, both during construction and in use will be supported. Sustainable drainage networks should be designed for ease of long term maintenance, as well as lifetime efficiency. Best sustainable on-site use should be made of materials arising from maintenance.

Further action required

- ▶ All partners to take forward the recommendations of the Beult and Teise Catchment Improvement Groups

A Sense of Place



Marden's countryside is important. The setting of the village in its traditional Low Weald farming landscape means more to residents than merely a nice view – it contributes to the overall wellbeing of the parish. The Marden Neighbourhood Plan recognises the need for development but this cannot be at the expense of Marden's unique setting and sense of place. This view is strongly supported by local residents and repeated at all the Marden Neighbourhood Plan Open Days and workshops. As one resident stated "We owe it to our future generations and our wildlife to protect the countryside that so many of us enjoy today".

In consultation MBC has confirmed that development should contribute positively to the conservation and enhancement of the landscape. The three inter-woven strands of visual integration, habitat conservation and biodiversity gain are addressed by policies designed to maximise integration and minimise any negative impact from additional development in this rural parish.

During preparation of this Plan, residents were asked to identify the characteristic features of the surrounding country and those features that they most valued. Historic elements of the landscape, orchards/hop gardens and older farm buildings, were considered the most characteristic features in 98% of the replies. They were also the most valued at 21% and 18% respectively. Physical elements of the landscape, including water, woodland, hedges and



flat/gently undulating land, were considered characteristic in 88% to 93% of the replies.

In consultation Natural England has referred to the iconic hedgerow landscape of Marden. The parish is fortunate that many field boundary hedgerows dating from at least the 19th century still exist on the ground. There are also many special trees which are considered 'locally notable', using the terminology of the Woodland Trust. Most are veteran oaks in heritage hedgerows, but there is also a fine yew in the churchyard. These all contribute to the sense of place enjoyed in the local residential environment or experienced when travelling around the parish on foot, by bicycle or on the roads. The benefits for wildlife may not be so obvious but are equally valuable and are addressed under the following Habitat Conservation heading.

The MBC's Landscape Character Assessment 2012, as amended 2013, describes the majority of the parish as Staplehurst Low Weald. "This is an historic landscape of small gently undulating grazed hedged fields with distinctive frequent mature and ancient English oak standard trees creating a strong sense of enclosure. Gently winding roads with wide lushly vegetated verges and ditches, colourful with cow parsley ... reinforce an intimate atmosphere.... Intensive orchard production is found on the fertile and often better drained loamy soils north east of Marden but also on heavier and wetter soils around Marden Beech and Marden Thorn and other pockets scattered throughout the area."

The Character Areas of the Beult Valley, Teise Valley and Sherenden Wooded Hills are self-explanatory, following the topography and soils. The Landscape Character Assessment recommends the conservation and enhancement of hedgerows in the Beult and Teise Valleys, the conservation and planting of new oak trees in the Sherenden Wooded Hills and the restoration of lost hedgerow boundaries in the Staplehurst Low Weald. There is therefore considerable opportunity for specific net gain for hedgerows impacted by development. However all proposals should also address the implications of maintenance and management in a sustainable manner.

Independent landscape consultants have advised MBC (2000, 2012) that past peripheral expansion of the village has created the appearance of "undistinguished modern housing estates" and "a rather untidy aspect around its periphery". The Landscape Integration Policy has been designed to ensure that future developments 'fit in' and are in keeping with the character and personality of the village and its surroundings. It is important to consider both the appearance of the new development from 'outside' and the views from 'inside' to beyond the built environment. For example, design of any artificial lighting systems should take account of their appearance when viewed from surrounding country and roads, both when illuminated and as features in their own right in daylight. Light overspill and adverse effects on wildlife should also be considered when determining the height, size and number of lighting columns.

On the basis of the foregoing evidence it is considered essential to conserve and enhance the natural environment and the landscape of the parish. Careful treatment of the village periphery is required to maintain and improve the appearance of the edge of Marden village, by avoiding suburbanisation and



sprawl, and minimising the visual impact on the surrounding fields and wider landscape. In an area with a wealth of established deciduous trees and shrubs it is not surprising that the public consultation response noted that screening with evergreens, walls or high, solid fences is not appropriate. Dense native species hedgerow planting is the preferred boundary treatment, as expanded in Policy NE5. These considerations of developments fitting in with their surroundings applies at all scales from large housing estates adjacent to the village to the conversion of individual rural buildings.

POLICY NE3 – LANDSCAPE INTEGRATION

All proposed developments should be designed to integrate into their surroundings in the landscape and contribute positively to the conservation and enhancement of that landscape. Dense hedgerow planting with native species is the preferred boundary treatment if the strengthening of existing hedgerows or restoration of lost hedgerow boundaries is not possible. Artificial lighting systems, if deemed necessary, require sensitive treatment to reduce visual intrusion and negative impacts on wildlife.



Habitat Conservation



"The best time to plant a tree is twenty years ago.

The second best time is now".

Chinese Proverb

The typical Marden networks of waterways, hedgerows and woodlands are essential to wildlife habitats, as well as contributing to the visual landscape. They are also valuable as wildlife corridors and stepping stones to facilitate the movement of animals, invertebrates and plants, encouraging diversity, and enabling response to external pressures such as development and climate change. Hedgerow replanting, restoration and new plantings can better connect the wider ecological network of natural areas and provide opportunity for a net gain consideration for lost habitat.

The rural, predominantly agricultural, parish has a wide range of ecological habitats; many of which are also of historic interest. There are two Sites of Special Scientific Interest: Marden Meadows, which is one of the best examples of unimproved neutral grassland remaining in the south east; and the River Beult, which is one of the few clay rivers in England which retains a characteristic flora and fauna. Wide areas of agricultural land are under agri-environment schemes, including the English Woodland Grant Scheme and Arable Assemblage Farmland Birds targets.

The parish is home to several individual species of interest including great crested newts, brown hare and dormice. Local wildlife sites are found adjacent to Marden Meadows and in deciduous woodland to the south of the parish. Any redevelopment of existing land under arable or top fruit production will displace a wide range of wildlife. Compensatory provision of places for shelter and hibernation together with food supplies to benefit invertebrates, birds and mammals will be need to be ensured.

The parish also has Priority Habitats as defined in the Kent Biodiversity Strategy 2015: Traditional Orchards, Ancient & Semi-natural Woodland, Ancient Replanted Woodland and Deciduous Woodland. The Biodiversity Opportunity Area of the Medway and Low Weald Wetlands and Grasslands includes the Teise and Beult valleys.

During preparation of the Neighbourhood Plan, residents were asked to comment on what they saw as the future challenges for the parish. Their main concerns covered voluntary initiatives on locally grown and sold food, nature conservation, building materials from local or sustainable sources and a reduction in water demand. However, nature conservation was deemed the most urgent issue. A directly comparable survey in 2006 ranked nature conservation sixth, showing the increasing interest and concern for this issue.

The retention or re-creation of historic field boundaries in the parish will contribute towards the retention and expansion of a local wildlife habitat network as well as retaining the continuity of the historic setting of field boundaries. Where relevant, new hedge planting is encouraged along these historic field boundaries. The use of traditional and native species of local provenance will minimise the import of plant pests and diseases, maintain the natural vegetation in the surrounding area, and ensure new planting blends with the existing landscape.

Local consultation responses drew attention to the timescale for integration of development once built. As one comment put it, "please don't cut down existing established trees.... Mature trees cannot be replaced in our lifetime by young saplings. They are not a 'quick fix' solution. We need green mature

trees in the village for our wellbeing". There was particular support for native species of trees and shrubs.

It is therefore important for all existing shrubs and trees not on historic hedgerow alignments to be considered for retention and incorporation in the landscape plan and open space provision of the development. If established habitats and visual features are fully protected during construction they can act as 'stepping stones' to maintain wildlife movements as well as act as reservoirs of plants and soil life. The Woodland Trust encourages the protection and retention of older and important trees and notes the benefits to the community, new residents and the developers' purse!



"Ancient and veteran trees are special because of their size, age or condition. Retaining these trees will enhance the value of any development. They will add a unique quality, giving it a sense of place or an 'air of respectable antiquity', creating character and distinction which will be appreciated by potential owners and their families Designing development around trees and woods with significant amenity, heritage and biodiversity value will foster good relationships with communities and local planning authorities. Time spent identifying and caring for all trees of importance will pay dividends in increasing the appeal and value of the site for clients and home owners A development should take a holistic approach to the wildlife features on site, on adjacent ground and in the wider landscape". (Woodland Trust, 2011*).

It is vital to mitigate the loss of wildlife habitat, to reduce the adverse effects on wildlife in the surrounding area and contribute to enhancing the special interest of adjacent and downstream habitat and species. Accordingly, all ecological site designations such as Local Wildlife Sites, Ancient Woodland and Sites of Special Scientific Interest are protected by planning legislation. However, all new development should actively support the aims and targets of the Kent Biodiversity Strategy¹, contribute to the Biodiversity Opportunity Areas and protect Priority Habitats. Developers are encouraged to consult the appropriate Catchment Improvement Group.

POLICY NE4 – BIODIVERSITY AND HABITATS

Owing to the unique setting of Marden in its surrounding landscape all new development is expected to support actively the aims of the Kent Biodiversity Strategy, to protect Priority Habitats and, where possible, contribute to the Biodiversity Opportunity Areas. A biodiversity net gain philosophy should be implemented so that any habitat or species loss is replaced elsewhere on-site, in excess of the amount originally lost. Local off-site re-creation is viewed as a last resort but the net gain principle would apply to ensure there is a positive impact from the new works.

**Ancient Tree Guide 3 - Trees and Development*

¹In 2019 MBC is in the process of developing a new Biodiversity Strategy for the Borough. This should also be consulted and appropriate action taken in due course.

Landscape Planting



As noted above all new planting on boundaries should be traditional, native species of local provenance. It should be locally specific to link development to the surrounding rural landscape. Careful choice of species likely to thrive in the available soil is obviously important but consideration should also be given to the seasonal range of drainage conditions both current and future. Priority should be given to species which, in combination, will optimise the provision of nectar, pollen, fruit and seed throughout the year. The plant species chosen should also provide shelter and protection for wildlife. Unfortunately the integrity of the landscape is vulnerable to a range of plant diseases and Marden is suffering the increasing effects of the untreatable ash dieback disease. Contemporary phyto-sanitary concerns should be addressed in species mix selection, planting and maintenance.

In planning and planting hedgerows adjacent to fields, sufficient space must be provided for dense hedges to grow to at least 2 metres wide, with a margin on each side for long grasses to grow at their base, as recommended by the Town & Country Planning Association and The Wildlife Trusts, 2012. All development proposals should include appropriate maintenance and management plans and adequate arrangements to ensure they are carried out.

All opportunities should be taken to reduce existing infestations of non-native invasive species, control pernicious weeds and prevent the spread or import of plant diseases.

POLICY NE5 – LANDSCAPE PLANTING

New landscape planting in Marden must be selected from native species of local provenance for visual continuity and to maintain the natural rhythms of the vegetation in the surrounding area. Priority should be given to species that provide food and shelter to wildlife. Adequate space must be allocated on the Site Plan to allow the planting to reach maturity without detriment to the amenity of the development such as encroaching on neighbouring property, excessive shading of gardens or interruption of external views.



Soil Conservation



The parish soils are underlain by the Weald Clay Formation with superficial deposits of alluvium in the river valleys. The slightly higher land consists of River Terrace deposits with sand and gravel. The valley soils have naturally high groundwater. Loamy and clayey soils cover the majority of the parish, slowly permeable and seasonally wet. Freely draining loamy soils are found on the ridge running across Marden Beech to Wanshurst Green and Underling Green.

On-site soil remediation techniques such as soil stabilisation should be used, as necessary, to ensure the existing soils on site can be made suitable for purpose. Appropriate soil conservation measures should also address the handling and temporary storage of soils, as well as preventing erosion, both during construction and until stabilizing vegetation is re-established. The objectives of the soil conservation policy are to retain the natural soil fauna and flora of the parish; to assist the establishment of new native planting; to reduce the spread of undesirable and potentially invasive plant material and soil-borne diseases, and to reduce off-site traffic movements associated with the import and export of soils and any other excavated materials.

POLICY NE6 – SOIL CONSERVATION

Development proposals should demonstrate sustainable on-site soil management and minimise the import of subsoil and topsoil and the export of any excavated ground materials.



Built Environment

Local Character



Marden is an ancient village with many historic buildings. Retention of these buildings has contributed to the character of the village. Some individual buildings are legally protected as listed buildings. There are 129 in Marden, 55 of which are in the village centre. The Church is Grade I, White Lyon House, Chainhurst Farmhouse and Great Cheveney are Grade II* and the remainder Grade II. The Marden Conservation Area covers much of the centre of the village.

There is a variety of architectural forms, styles and materials represented by buildings constructed and developed over hundreds of years. There are examples of pre-15th century timber-framed buildings together with tile hung façades and many different styles of brick-built properties constructed from the 18th century through to the present day.

The conservation area was designated in 1977. MBC has undertaken Conservation Area Appraisals and Management Plans in some parts of the Borough, but this has not yet been done in Marden. The process is recommended by Historic England and a plan for Marden is now a matter of urgency.

Residents at the Open Days supported the need to carry out a Conservation Area Appraisal and Management Plan and the need to incorporate additional areas. A review of the conservation area was then undertaken as part of the Marden Neighbourhood Plan workshops that identified several areas which should be considered for inclusion: Albion Cottages, the School and Memorial Hall, Railway Cottages and parts of the east side of Goudhurst Road.

A number of the most recent major housing developments included large three storey blocks of flats. The introduction of such buildings are inappropriate and would have a detrimental impact on the rural character of Marden. Strong opposition from the Parish Council led to amendments to reduce the overall height and design of the structures and this was welcomed.

This Plan does not seek to prevent the development of three storey buildings – the use of roof spaces with small dormer windows is a typical feature of the Kentish landscape. The Plan would therefore seek to support development of a suitable scale and height that respects and enhances the Wealden character of Marden.

POLICY BE1 – LOCAL CHARACTER

Development proposals should be designed to protect the fabric and setting of any designated and non-designated heritage asset and respect and enhance the existing character of the village. Development must be both visually and functionally sympathetic to the existing styles and materials – examples of which are illustrated in this plan, in order to maintain and enhance Marden's sense of place.

Further action required

- ▶ Marden Parish Council to lobby MBC to undertake a Conservation Area Appraisal and Management Plan for Marden.

Residential Amenity



There was a strong consensus from the open days for new housing development and residential extensions and alterations to blend with the existing vernacular style, to use good quality materials and incorporate features of interest. Adequate off-road parking and garden space were also considered to be essential elements of all new developments. There was opposition to any further gated communities as a principle, although it was acknowledged that other factors may need to be considered. For example, the need for pedestrian safety was an over-riding consideration in the provision of gates at Rookery Court. Further support to this approach was given by residents at the 'Village Boundaries' workshop on 21 September 2013.

The Marden Design Statement identified design features and materials that characterise the parish. It stated: *"It is clear that there is no single Marden building style. Each period has added to the variety of village and farm buildings. New development should not attempt to replicate exactly any one of the styles represented: design should be contemporary but sympathetic with its immediate surroundings – and, more broadly, with the Marden character as a whole"*. Its exemplars are re-stated within the plan.

POLICY BE2 – RESIDENTIAL AMENITY

New housing development and residential extensions and alterations should provide suitable residential amenity for residents, both existing and future, in terms of privacy, light and outlook. Proposals should include the provision or retention of adequate garden space and allow through routes for pedestrians, cyclists and vehicles (ie no physical barriers).

Most people only come into contact with the planning system when they or their neighbour submits a planning application for a domestic extension. Although the impact of such extensions is by their very nature likely to be limited, aspects such as intrusive external lighting can have a great impact on the quality of life of those directly involved. It is very important this is recognised by the Marden Neighbourhood Plan, with good neighbourliness being essential to the wider village community.

Traditional Materials and Designs

Weatherboarding

Traditionally white on domestic buildings and black on farm buildings (also when converted). Either full facade or on upper elevations only.



Peg Tiles and Bricks

Mainly multi-hued, ranging from bluish-red to reddish-brown. Tiles generally darker than bricks. Hung on part or full facade. Historically made from local clay.



Special Features and details

Roof Profiles

Houses of all ages (and old farm buildings) typically have hipped or half-hipped roofs. Clay tiles are the norm.



Oast cowls

(ubiquitous)



Weather vane and clock

(Marden Bowls Club)



Exposed beams

(High Street)

Gable end detailing

(Marden Thorn)



Wooden porches

(Goudhurst Road)

Metal Porches

(Chantry Road)

Special Features and details (cont'd)

Decorative Railing

(West End)

Brick wall decoration

(Stanley Road)



Chimney cowl

(Cherry Orchard)

Arch windows

(Cherry Orchard)



Street Furniture

Village sign

Milestone

Mounting block



Old fingerpost sign

Signs old and new



Bridge nameplate

Parish Pump

Church wall seat



Sustainable Construction

"You may be able to fool the voters, but not the atmosphere"

Donella Meadows

(Environmental Scientist 1941-2001)



The sustainability of all development must underpin the basic design approach and be fundamental to all schemes. The population in the South East will grow and so the demand for natural resources to power and service our homes and businesses will become even greater. Planning has a key role in helping to shape the places in which we work and live and to mitigate the impact of climate change.

The NPPF supports the transition to a low carbon future. Therefore, energy efficiency improvements to existing buildings are to be encouraged and local design requirements for sustainability which aim for zero carbon building should be incorporated.

It is recognised that the effects of climate change will be central to development across the borough. The Climate Change Act 2008 sets two legally binding targets of 34% reduction in greenhouse gas emissions by 2020 leading to 80% reductions by 2050. MBC has adopted the Kent Environment Strategy 2016 which supports a low carbon transition. There are likely to be further changes in legislation and guidance relating to measures of sustainability, and this is expected to continue so it is important to keep following best practice.

The Marden Neighbourhood Plan recognises and fully supports developments which show high levels of sustainability. Residents are only too aware of surface water management and quality issues in the parish – see policies NE1 and NE2. Similarly, the installation of small-scale renewable energy schemes at both domestic and commercial level is encouraged. There are an increasing number of local examples of good practice. New buildings can also incorporate simple measures to encourage wildlife habitats. The inclusion of bat and nest boxes and bee bricks for example.

The use of rainwater harvesting is recommended for all new development. The use of solar thermal technology, ground and air source heat pumps and heat recovery systems are encouraged, with the ultimate aim of achieving minimal energy use through the use of passive house design.

POLICY BE3 – SUSTAINABLE CONSTRUCTION

All development must be based upon the principles of sustainable construction and accord with the most up-to-date guidance and best practice. Support will be given to development that provides or incorporates low or zero carbon technologies providing development conforms with other policies in the plan.

Rural buildings



Marden is a rural parish and accordingly most of its land lies beyond the main village settlement. The parish has a multitude of rural buildings in the countryside, mostly associated with agricultural use. The changes to agricultural working practices means that many of these buildings are no longer needed for their original purpose. We are all familiar with the oast houses and barns that have been converted to residential use.

The conversion of agricultural buildings is, in principle, acceptable. The NPPF encourages the re-use of existing resources, including the conversion of existing buildings. It also stresses the desirability of sustaining and enhancing the significance of heritage assets and putting them to viable uses consistent with their conservation. This Plan requires extensions to existing rural buildings to be sympathetic and respect local building styles and materials. The MBC Local Plan allows for the conversion of rural buildings outside settlement boundaries, providing the buildings are structurally capable of conversion, respect the rural character and provide adequate residential amenity with off-road parking.

POLICY BE4 – CONVERSION OF RURAL BUILDINGS

Support will be given to schemes for the conversion and alterations of existing rural buildings which respect the character of the building and its wider rural setting in Marden. This is subject to it not overwhelming or destroying the original form of the building and it having no adverse impact on wildlife habitat and the character and residential amenity of neighbouring properties.

Legislation introduced in 2015 has given greater permitted development rights to convert former agricultural buildings to other uses. This means that agricultural buildings can be converted without the submission of a planning application, merely a prior notification.



Farm Buildings



Marden is an agricultural and horticultural parish, with the production of arable, top and soft fruit, sheep, hops and viticulture. It is recognised that the farming community has to keep abreast of new and emerging methods of production, storage and marketing facilities to maintain its viability. This may result in the introduction of new buildings into the countryside. Such developments, either temporary or permanent, will be expected to be sited and designed to be compatible with their surroundings. The inclusion of small scale renewable energy systems, such as roofs with photovoltaic panels, is also encouraged.

The MBC Local Plan aims to limit new agricultural development to only those structures necessary for agricultural purposes and to minimise any adverse impact on the amenity of nearby residents and the character of the countryside. Many agricultural buildings can be erected under permitted development, but for those buildings that require the submission of a planning application the following policy applies.

POLICY BE5 – NEW FARM BUILDINGS

Support will be given to new agricultural and horticultural buildings that have been designed and sited to minimise any adverse impact on residential amenity; the character of the wider countryside; be sympathetic to local surroundings; and respect the historic character of the site. Structures should use sustainable construction materials, methods and include small scale on-site renewable energy schemes.



Marden is an important fruit production area and, as such, large numbers of temporary workers are often required, particularly at harvesting time. Historically workers have come from the travelling community, the student population, or in more recent times, from Eastern Europe. Many farming units also have sophisticated storage and packhouse facilities which can operate for most of the year. In recent years, the provision of mobile home accommodation has proved to be the most practical form of workers' accommodation and the need to house seasonal agricultural and horticultural workers for temporary periods in the countryside is understood.

POLICY BE6 – SEASONAL WORKER ACCOMMODATION

Support will be given to the provision of temporary accommodation for seasonal agricultural and horticultural workers which is sited and designed so as to minimise any visual impact on the wider countryside and be permitted on a temporary basis where there is a proven need.

In Marden, like many other rural settlements, small pieces of agricultural land have been sold to adjacent residential landowners. It is important that local residents are aware that such pieces of land will require planning permission for a change of use before they can be used as a domestic garden. Planning applications for such works must consider the loss of agricultural land and the impact of the change of use on the character of the countryside. A proliferation of such changes in use is likely to lead to an unacceptable suburbanisation of the countryside, if allowed to go unchecked.

Community Facilities

"The pub, the football match, the back garden, the fireside and the 'nice cup of tea'."

George Orwell (Novelist 1903-1950)



Rural settlements rely heavily on community-focused services. Marden has a very active community life with many different groups and clubs. Residents value the village for its great 'community spirit'. The village has a wide variety of amenities: retail, social, leisure, sports and healthcare. The growth in housing will increase the demand for these facilities, so their retention and necessary expansion is vital.

The MBC Local Plan seeks to resist the loss of local shops and facilities in Rural Service Centres, whilst supporting the development of new shops and community benefits. This aim is supported by the Marden Neighbourhood Plan to help retain and promote a thriving, sporting, creative and cultural life for people of all ages so that everyone can lead a more active and independent life.

Marden has a number of publicly accessible buildings that require regular maintenance. The Marden Memorial Hall provides a community venue for many groups and societies as well as the Pre-School Playgroup. The roof was replaced in 2015 to ensure the long-term viability of the building.

During 2018 there has been a notable increase in anti-social behaviour among young people in the village. There is currently a limited youth service and no dedicated facility for young people. The continual expansion of the community means that a dedicated youth facility has become increasingly important.

"Marden has 60% of young people between the ages of 8 and 19; strong evidence of youth facilities are needed in Marden; a youth club is vital for making young people feel supported within their community." – Youth Worker – Natalie Penfold 2018)

Marden is also fortunate in having a number of sporting facilities. The playing field, which incorporates a football pitch, is owned and managed by the Parish Council. Marden Minors have a pitch in Pattenden Lane. The Marden Hockey and Cricket Club, Blue House Cricket Club, Tennis Club and Bowls Club are operated as private clubs but are, however, open to all residents of Marden and the surrounding area. These organisations are always looking for funding to improve their facilities.

The parish has three public houses and a village club which are all popular places to gather, drink, eat and be entertained.

Marden Library and Heritage Centre has been identified at the Marden Neighbourhood Plan open days as a much-valued community amenity.

Discussions were held between KCC, the Parish Council and the Marden History Group regarding the organisation of the existing library service. This included ways to increase usage and reduce overheads. The Heritage Centre is staffed by volunteers and greatly adds to the social cohesion of the village. Support for this facility is essential, locally and nationally, it having been awarded a National Archive recognition. Marden Neighbourhood Plan seeks to maximise the benefits from any developer contributions arising from new development in the parish to support the ongoing provision of the Heritage Centre and all other village amenities¹.

¹Please see the current Marden Parish Council Infrastructure Spend Plan.

POLICY A1 – COMMUNITY FACILITIES

Development proposals that help to sustain the existing community facilities and create new facilities either directly through developer contributions or indirectly by encouraging local spending will be supported provided development conforms with other policies in the plan. Any new development should prioritise dedicated youth facilities.

Further action required

- ▶ KCC, Marden Parish Council and the Marden History Group to continue working together to secure the future of the Marden Library and Heritage Centre.
- ▶ KCC and Marden Parish Council to continue working together to ensure Youth Facilities are provided within the parish.

Open Space



Marden is fortunate to have a number of public open spaces as well as a variety of sport and recreational amenities. Open space, be it in the form of streets, parks, squares or open fields, is critical to the well-being of residents. The importance of these areas is expected to be recognised by any new development and new spaces to be carefully designed to complement those that already exist within the village. As one resident stated, “Our young people need space to grow as well as our village.”

Marden Parish Council owns and maintains the Marden Playing Field with its play equipment, football pitch and changing rooms. The Parish Council owns and maintains Southons Field with its beautiful specimen trees and trim trail. The Parish Council also owns and operates the Marden Cemetery that is a well-maintained and attractive area, together with the land to the rear in order to safeguard the land for any future expansion.

New areas of open space have been created on recent housing developments. The new space created on The Parsonage development is recognised in the MBC Local Plan Policy OS1(8).

The parish also includes valuable areas of open space that are in private ownership such as Millennium Walk and Bridgehurst Woods. The loss of such areas to development is to be resisted, unless equivalent or better open space areas are guaranteed.

It is essential that we continue to protect, maintain, improve, enhance and existing areas of open space in the parish. This is particularly important for those areas located close to concentrations of housing. Open space can also have a positive impact upon the quality of the built environment, be of ecological value and engender physical and social interaction and wellbeing that is vital for community cohesion.

The importance of open space was identified in both the Marden Design Statement 2001 and the Marden Community Plan 2007. More recently, at the Marden Neighbourhood Plan open days, residents again identified the



importance of open space. Local people are best placed to help decide what is needed in their environment and should have greater community involvement in the management of green and blue facilities. The Marden Neighbourhood Plan, therefore, seeks to maintain and improve the existing and valued areas of open space and to encourage the provision of additional areas. This will ensure Marden is a greener, healthier, more attractive and welcoming village.

The NPPF requires planning policy to be based on robust and up-to-date assessments of the needs for open space, and sports and recreational facilities. National policy also encourages the creation and enhancement of a network of open spaces and natural habitats and the protection of existing areas of open space and landscapes.

POLICY A2 – OPEN SPACE

All major development* should provide areas of amenity, recreation, woodland, ponds or other water features and these to be retained for community use. Links should be provided between areas of open space, community facilities and the public rights of way network, with management plans confirming operating responsibilities put in place to safeguard the future retention of these areas.

**"NPPF Definition – Major Development - For housing, development where 10 or more homes will be provided, or the site has an area of 0.5 hectares or more. For non-residential development it means additional floorspace of 1,000m² or more, or a site of 1 hectare or more, or as otherwise provided in the Town and Country Planning (Development Management Procedure) (England) Order 2015"*



Education

“The foundation of every state is the education of its youth”.

Diogenes (Greek Philosopher 400 BC)



Every community must have the facilities to provide its residents with a good standard of education. Marden has an excellent primary school that has consistently achieved good reports with OFSTED. There is a wide range of secondary education within reach of Marden. KCC's secondary school transport arrangements are, at present, denying real choice for some of Marden's children who attend secondary schools where the only access from Marden by public transport is via train eg Paddock Wood, Tonbridge and Tunbridge Wells, and do not benefit from any subsidised travel arrangements. This is an issue for low income families who cannot afford the rail fare.

The NPPF states that a sufficient choice of school places must be available to meet the needs of existing and new communities. It states that the local planning authorities should take a proactive, positive and collaborative approach to meeting this requirement, and to development that will widen choice in education. Great weight must be given to the need to create, expand or alter schools and work with school promoters to identify and resolve key planning issues before applications are submitted. The MBC Local Plan lists education among the priorities for residential, business and retail development where infrastructure is delivered through Section 106 agreements.

Marden Parish Council has always had a good relationship with its village primary school and is firmly of the opinion that village children should have the opportunity to attend their local school and be able to continue their secondary education within a reasonable distance from their home. Until 1994, the village school coped with expanding numbers of entrants with mobile classrooms in the grounds. However, the school building was then extended so that all rooms were under one roof. At the time outline plans were laid down for further expansion, but the necessary funds were not available from KCC. As a result, the school once again had to resort to the use of mobile buildings.

KCC announced plans in 2016 for improved and extended facilities at the school, but the capacity issue must be kept under review in the light of the recent housing development in the village. It maybe that in the future, as the population of the village grows, a new site for the school will be needed, which could incorporate a nursery for pre-school children.

As with many schools there is traffic congestion at arrival and departure times that will only be exacerbated by further expansion. The congestion leads to safety issues that must be addressed. Residents raised these issues at the open days and during a consultation undertaken in early 2017 and again at a parking consultation held in February 2018. The Parish Council has been working with KCC Highways to identify solutions to alleviate the problems, but it is unlikely these will fully mitigate the safety issues unless the school is re located to a new site, off the main road, where there is capacity for safe off road parking.

Marden has a Children's Centre which was under threat of closure in 2016 but the Parish Council and local residents were successful in preventing this from happening.

Marden also has a successful pre-school playgroup, which has served the community since 1967, with strong links to Marden Primary School and the Children's Centre. Pre School education is provided for children aged 2 -5 years during term time, 24 hours per week and 38 weeks per year. This is a non-profit

making organisation and is currently housed in the Marden Memorial Hall, which has limited capacity and is used by many other village organisations, as it is the main community hall for the village. As the population of Marden grows demand is now outstripping supply and the playgroup is unable to offer places to all those applying. Additionally parents are looking for day care, both full time and outside term time. Marden Pre-School Playgroup is committed to finding suitable facilities to enable it to become a stand-alone nursery allowing them to open for longer hours and cater for more children.

POLICY A3 – PRIMARY EDUCATION

Support will be given to developments that provide KCC with funding to ensure that Marden Primary School has the additional capacity and resources to give all local children a good standard of primary education providing development conforms with other policies in the plan.

Further action required

- ▶ Marden Parish Council will continue to lobby KCC about subsidised travel arrangements to secondary schools attended by Marden children.
- ▶ KCC to ensure that existing S106/future CIL developer contributions are used proportionately to support the provision of secondary school education for Marden children.
- ▶ Marden Parish Council to explore possible provision for nursery care and education within the parish of Marden to provide good quality facilities for pre-school children.

Healthcare



In 2014, the Marden Medical Centre provided primary medical care services to 5734 patients. The list has now grown to the 2018 level of 6435 (12% increase) and would be expected to reach some 7200 to 7400 in 2020/21, when the present phase of major residential development currently approved, should be complete. An expected increase in patient numbers of 25 to 30% in less than 7 years.

In 2019 the existing Marden Medical Centre is already close to capacity and the building should ideally be extended to meet the 2020/21 patient numbers. At the MNP Open Days residents have repeatedly raised the lack of parking available at the Medical Centre.

The Medical Centre is also under pressure to increase the range of services provided.

Marden is expanding from a largely rural village into a Rural Service Centre with an increasingly diverse population. This has caused extra demand, not just in terms of the patient numbers but also from the higher incidence of health and social problems. The additional health related social and support services, such as midwives, health visitors and the Children's Centre are already suffering the results of resource limitations. The services are becoming inadequate to support the increasing and changing population effectively.

In addition, the current NHS 5-Year Forward Plan and West Kent Community Care Group's (WKCCG) Sustainability and Transformation Programme (STP) call for a co-ordinated and holistic approach to health and social care delivered locally. If Marden is to meet this requirement, the Medical Centre will need to expand clinical, social and associated services and work with adjacent GP practices to provide a co-ordinated response, putting increased pressure on medical, administrative and support staff and facilities.

However, the Medical Centre operates from a building that will struggle to meet future demand due to its lack of space on a constricted site. The Neighbourhood Plan policy supports planning and possible development for new facilities on a separate site(s) and, in the short term, the extension of the existing facility to meet more immediate needs.

The Medical Centre has received funding in the form of S106 contributions from the first new housing developments in the village. Future development will also need to make appropriate contributions in order that the Marden medical services can meet the demand resulting from the associated increase in services and patient numbers.

Marden is also fortunate to have the Marden Dental Surgery which is a thriving practice with an excellent reputation.

POLICY A4 – HEALTHCARE FACILITIES

Support will be given to proposals that help provide the Health Care Authority to maintain and enhance existing healthcare provision and encourage the expansion of health, wellbeing and social care services in Marden through extended and/or new healthcare facilities.

Water Supply and Sewerage

The advice relating to the MBC Local Plan in the Sustainability Appraisal Scoping Report (2009) is equally applicable to the Marden Neighbourhood Plan. It notes that Maidstone is located in a waterscarce area, which will be exacerbated due to climate change and future growth and development. Advice relating to water resources includes the need to ensure that the distribution and location of new development takes the water supply and sewerage infrastructure into account.

The government's Water Strategy for England (2008) sets out the government's vision for the water sector by 2030. The Strategy requires planning authorities to work closely with water companies and the Environment Agency on the timing and numbers of new households in areas likely to see the greatest growth. It addresses a range of water-related issues, including managing water demand through increased water efficiency and reduced water wastage; enhancing future water supply through new infrastructure; and addressing water quality through tackling pollution.

Marden Parish Council has been concerned that water infrastructure failures are not being rectified and that essential new infrastructure may not be provided. The Parish Council does, however, welcome the 2018 improvements that were carried out by South East Water (water supply) and Southern Water (sewerage).

Whilst dealing with existing water infrastructure problems lies outside the planning regime, developers, planners, South East Water and Southern Water are urged to take a holistic approach to avoid any further detriment to the existing sub-standard systems and, preferably, work together to improve these before, or during, the construction of new infrastructure associated with new developments. The Parish Council has been active in meeting with service undertakers to ensure improvements are carried out.

POLICY In1 – WATER SUPPLY/WATER SUPPLY AND SEWERAGE

New and improved utility infrastructure will be encouraged and supported in order to meet the identified needs of the community, subject to other policies in the plan.

Transport



We all need to travel; to work, to school, to shop, to visit friends and family, for recreation, and a host of other reasons. However, the consequences of car and lorry traffic, and the limited range of available alternatives, are frequently identified as amongst the biggest issues affecting people living in rural areas. Marden is no different.

The NPPF states “transport issues should be considered from the earliest stages of plan-making and development proposals.” It also requires that “appropriate opportunities to promote sustainable transport modes can be, or have been, taken up, given the type of development and its location” are ensured.” The MBC Local Plan states that MBC and its partners will manage and enhance the borough’s transport infrastructure, develop strategic transport links to and from Maidstone and connections to the Rural Service Centres, improve highway safety, promote sustainable travel, promote a high-quality pedestrian environment, manage the provision of car parking and ensure that the transport network provides inclusive access.

The preparation of the Marden Design Statement between 1998 and 2001 involved several rounds of public consultation, and resulted in a number of transport related recommendations. Marden held a traffic consultation in November 2002, with the main issues raised being traffic speed, heavy lorries and bad parking. Marden Parish Council held a further follow-up workshop in November 2003. This explored a village traffic calming scheme, improved signage and lorry restrictions, and changes to parking restrictions. The results were submitted to Kent Highways. Many of the proposals were taken forward by the Parish Council as the 2006 Marden Traffic Calming Scheme. This formed part of a package of traffic calming measures adopted by the South West Maidstone Traffic Management Partnership (TRAMP). This resulted in a traffic calming scheme that secured funding from KCC, but which was eventually cancelled.

Further work was undertaken as part of the 2007 Marden Community Plan. Three open days were held and residents identified traffic calming and other highways issues, improved rail and bus services and the encouragement of walking and cycling as priorities. In 2008, the Parish Council submitted the results of these ongoing consultations to the KCC’s 2008 Speed Limit Review Demonstration Area, but again, local recommendations went largely unheeded by the highway authority.

At the 2013 and 2014 Marden Neighbourhood Plan Open Days and Workshops residents identified the main transport issues as bus services, train services, the road network and public rights of way. Residents identified a wide range of potential improvements for delivery in connection with future development. There was support for the following:

- public bus services, possibly in partnership with large employers in Maidstone (e.g. KCC, MBC) with access to town-centre shops, amenities and Maidstone Hospital;
- a community bus operation;
- additional station car parking;
- improvements to village parking, particularly at the school;
- junction improvements, particularly at Church Green/Pattenden Lane and High Street/Maidstone Road;



improved cycle safety measures, including the provision of additional off-road routes;

footway improvements particularly the need for resurfacing and additional dropped kerbs;

the designation of 'quiet lanes'.

In February 2018 a parking consultation with residents and businesses was carried out. The results indicated that parking restrictions needed to be increased and at the time of writing MBC has issued a Draft Traffic Regulation Order to add additional no parking areas and amend some existing no parking times.



The MBC Local Plan originally sought to provide a park and ride at Linton Crossroads. This was wholeheartedly welcomed by local residents who experience great levels of congestion when travelling to and from Maidstone. The Marden Neighbourhood Plan is disappointed that this site has now been rejected. Nevertheless, should an alternative site on the A229 be found then a bus service linking the town centre with the park and ride site could be extended to Marden station. This could be used by Marden residents travelling into and out of Maidstone and those residents of south Maidstone who currently travel to Marden by car to catch the weekday commuter trains. This could provide a solution to two problems.



As in all rural villages, not all dwellings in Marden have adequate off-road parking. This leads to residents parking on the highway which, when added to visitor and commuter parking, leads to congestion and other highway safety issues. This is a constant concern to residents.

The Parish Council is asked to comment on a variety of planning applications. A recurring subject is the conversion of garages, often integral, which results in the loss of potential on-site vehicle parking spaces. In reality, however, it is recognised that integral garages are seldom used for vehicle parking and the desire of residents to convert garages is understood as it is a relatively cheap and easy way of creating extra habitable space. Nevertheless, this can lead to increasing problems associated with on-street parking that must also be recognised and this can prove of great concern to other residents. It is therefore important that a balance is found.

It is recognised that many modern developments incorporate shared driveways and private access roadways. The management of these arrangements is beyond the direct control of the planning system, and not being part of the adopted highway is beyond the control of the highway authority. This has the potential to lead to neighbour conflict. The Marden Neighbourhood Plan, therefore, urges housing providers to consider the ongoing management and maintenance issues this design feature can raise.

POLICY In2 – SUSTAINABLE TRAVEL

Support will be given to developments designed to maximise travel on foot and by cycle and that provide direct links to village facilities and public transport services via off-road and lightly trafficked routes, or through improvements for non-motorised users on busier existing routes. Developments should not hinder existing walking and cycling routes unless a convenient alternative route is provided. Major sites should be designed to provide through routes for pedestrians and cyclists where this would help improve non-vehicular access from adjacent housing or business premises and to facilitate links with any nearby public rights of way or open space.

POLICY In3 – ADDITIONAL TRAFFIC

Developments generating additional traffic should be located only where: (a) direct access to suitable roads is either already available or will be provided before the use commences or (b) mitigation measures are provided to reduce traffic impacts on otherwise less suitable roads to an acceptable level.

POLICY In4 – STATION

Support will be given to proposals to enhance facilities at Marden Station including any development required to meet increased demand providing the proposal accords with other policies in the Plan.

Further action required

- ▶ Station infrastructure stakeholders (including Network Rail, train operating company, Department for Transport, KCC and Marden Parish Council) to pursue enhancement opportunities including additional station parking and step-free access to the 'down' platform.
- ▶ Bus infrastructure stakeholders (including bus operating companies, KCC, MBC and Marden Parish Council) to pursue enhancement opportunities including additional bus services, new or replacement bus stop signage, road markings and bus shelters.

Housing

"It is the liberty to have a home of your own, to do what you like in your spare time, to choose your own amusements."

George Orwell (Novelist 1903-1950)

The Marden Design Statement 2001, which was formally adopted as Supplementary Planning Guidance by MBC, no longer forms part of the borough's Development Plan but is still used by the Parish Council and others as valuable guidance. The Marden Design Statement 2001 was the result of a parish wide analysis and produced specific guidance on a number of issues. This document stopped short of specific land allocation for housing development.

The intention was always to produce a second document to take the next step and identify sites which would be suitable for particular development types. This was originally envisaged as a parish plan, which then became a Neighbourhood Plan following the enabling legislation.



Unfortunately, there were numerous delays to the production of Maidstone's Core Strategy, now the MBC Local Plan, to replace the Maidstone Borough Wide Local Plan 2000. This has, in turn, delayed progress on the Marden Neighbourhood Plan.

Marden residents have always been aware of the pressures for development in the village, particularly the pressure for housing development. It was, therefore, one of the key aims of the Neighbourhood Plan to assess those sites which residents considered to be the most suitable for housing. This was one of the features of the first Marden Neighbourhood Plan Open Day in 2013. This was timed to follow the MBC 'call for sites' in November 2012 – a previous exercise having been undertaken in 2009. This process invited landowners and developers to put forward to MBC sites that could be considered for housing development.

The Marden Neighbourhood Plan Steering Group provided information on the location of the sites and asked local residents to consider the suitability of those sites for development. This process was repeated at the second Marden Neighbourhood Plan Open Day in 2014. The intention was to submit the results to MBC to use in the formulation of planning policy, and then through the adoption of the Marden Neighbourhood Plan, to be used for site specific development allocation.

The numerous delays in the production of the MBC Local Plan and its housing allocation, the inability of MBC to demonstrate a 5 year supply of housing, together with the thrust of the NPPF to encourage sustainable development has resulted in developers submitting schemes for large housing developments in Marden in advance of the adoption of the MBC Local Plan and Marden Neighbourhood Plan. This is of deep regret to the Steering Group, the Parish Council and residents. At the time of writing a further 'call for sites' is being carried out.

Full planning permission has been granted for nearly 600 dwellings over six sites. The Marden Neighbourhood Plan Steering Group and the Parish Council has worked hard to try and ensure these developments are well designed and has fought to maximise the benefits to Marden, particularly targeting developer contributions and the provision of affordable housing.

List of Sites (see Planning Policies and Further Actions Map at Annex 1)

Highwood Green – 110 dwellings

The Parsonage (including Vicarage Field) – 209 dwellings

Windsor Meadow – 86 dwellings

Appledown Grange – 44 dwellings

Old Marden Cricket and Hockey Club site – 124 dwellings

Further action required

- ▶ For clarity, MBC to modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) at the next periodic review to encompass the major Highwood Green housing development given planning permission in 2012 and completed in 2017 within the settlement boundary (refer to area FA1 on the 'Planning Policies & Further Actions' map.)
- ▶ Marden Parish Council and the Marden Neighbourhood Plan Steering Group to monitor progress and keep residents informed of the 2019 'call for sites' exercise.

Affordable Housing



Affordable housing provides housing for sale or rent, for those whose needs are not met by the open market (including housing that provides a subsidised route to home ownership and/or is for essential local workers). Affordable housing includes affordable housing for rent – where the rent is set at least 20% below local market rent and usually where the landlord is a registered provider. Affordable housing as starter homes – aimed at those with a particular level of income. Affordable housing as discounted market sales housing – where housing is sold at a discount of at least 20% below local market value and other affordable routes such as shared ownership.

Marden's need for affordable housing has been proven through a series of Housing Needs Surveys and has been consistently supported by residents (and others with Marden connections) at Neighbourhood Plan Open Days.

The MBC Local Plan states that on housing or mixed use development sites of 11¹ or more residential units or a combined floorspace of greater than 1000m², affordable housing will be sought at a target rate of 40% for Rural Service Centres.

The NPPF requires the needs of different groups in the community to be assessed and reflected in planning policy, including those who require affordable housing. This is welcomed. The MBC Local Plan also provides for affordable local needs housing on rural exception sites. The policy, however, relates to development outside the Rural Service Centres.

The MNP suggests that it is unlikely that all the need for affordable housing can be met through the recent housing development sites, particularly considering the length of the plan period. Therefore the following policy is required.

POLICY In5 – AFFORDABLE HOUSING

Support will be given to the development of rural exception sites for local needs housing where a proven need has been demonstrated, and the development is of a suitable scale, design and location.

Housing for Older People



The Marden Neighbourhood Plan recognises the need to provide well-designed comfortable homes for all, and the necessity to meet the housing needs of older people. The MBC Local Plan seeks to provide for future housing that meets the changing needs of the borough's population, including provision for an increasingly ageing population. This is supported by the NPPF.

The projected growth in the over-65 population means that housing will need to provide accommodation suitable for a range of mobility needs. This may require less conventional internal layouts and special consideration given to the siting of such homes.

The empirical research of Marden Neighbourhood Plan members has revealed the importance of siting when developing housing for older people. The need to see the outside world passing by the window has been highlighted as a primary requirement. This is particularly relevant for sheltered housing schemes in order to provide the visual stimulus so valuable to residents with restricted mobility.

¹ NPPF 2018 uses a threshold of 10 or more.



Consultation with residents has demonstrated overwhelming support for the provision of bungalows.

There are currently five developments designed for older residents in the village; three of which are owned by Golding Homes (a local housing association), and the other two are privately owned. The MBC Local Plan seeks to include a proportion of affordable housing to be for retirement housing and extra care homes. It also encourages the development of nursing and care homes in Rural Service Centres.

POLICY In6 – HOUSING FOR OLDER PEOPLE

Support will be given to development which provides housing suitable for older residents. This may include smaller bungalow units sited where occupants are provided with a vibrant and interesting view and within easy reach of services, amenities and natural areas where development conforms with other policies in the plan.

Housing for Gypsies and Travellers



The need to provide well-designed and appropriately-sited homes for all includes every section of our community. The Marden Neighbourhood Plan therefore recognises the need to provide well-sited accommodation for those gypsies and travellers with established links to the parish.

Gypsies and travellers are currently defined as persons of nomadic habit of life whatever their race or origin including such persons who, on grounds only of their own or their family's or dependants' educational or health needs or old age, have ceased to travel temporarily but excludes members of an organised group of travelling show-people or circus people travelling together as such.

Marden has an established Romany population. The Romany culture is celebrated in the South East Romany Museum founded by the Brazil family. The museum has a fine collection of decorated caravans, traps and carts, all restored using traditional craftsmanship.

Marden has a socially rented gypsy and traveller site at Stilebridge. The site is owned by MBC and managed by KCC. The parish also has a number of privately owned sites in Tilden Lane, Summerhill Road and Park Road. The MBC Local Plan also allocates land at Oak Lodge.

Marden Parish Council has links with the existing Stilebridge site and is trying to facilitate environmental improvements, particularly the creation of a grassed amenity area. The site, operating with 18 designated pitches, is near or at full capacity. Existing residents, the Parish Council and the Marden Neighbourhood Plan Steering Group will resist any proposal to expand this site when a more even distribution of new sites across the borough would be more appropriate.

There is a good relationship between the settled and travelling residents of Marden. The historic links between settled and travelling families has helped to create an integrated community. Accordingly, Marden Parish Council has favourably viewed planning applications for small gypsy sites to accommodate travellers with local connections.

Marden Parish Council has adopted specific guidance in assessing planning applications for gypsies and travellers.

Marden Parish Council Planning Guidance Note for Gypsy Caravan Sites (2017) states: Marden Parish Council appreciates the significance of the gypsy way of life in dealing with gypsy related planning issues. The Parish Council is aware of the need to balance the potential impact of a proposal against the needs and personal circumstances of the applicant.

When responding as a consultee to the Local Planning Authority, usually MBC, on gypsy related applications the Parish Council will consider the following:

The impact of a planning application in terms of its siting and potential effect upon the residential amenity, character, landscape, agriculture, conservation and highways of the area.

The gypsy status of the applicant, any relevant personal factors and any proven links with Marden Parish which may render the application exceptional.

Suggested conditions:

- 1 Only on a temporary basis (3 years)
2. Removal on cessation of use for residential
3. Limited permission to named persons only

POLICY In7 – HOUSING FOR GYPSIES AND TRAVELLERS

Support will be given to the development of small scale gypsy and traveller sites that provide adequate levels of residential amenity of the occupants and do not result in unacceptable harm to the residential amenity of the existing neighbours, the character of the countryside or the biodiversity of the wider area.

Further action required

- Marden Parish Council and the Marden Neighbourhood Plan Steering Group to monitor the distribution of planning permissions for new gypsy and traveller sites across the borough.

Business and Employment



Marden is fortunate in having a range of businesses offering employment opportunities. The village has retained some of its retail outlets and has offices, industrial and commercial operations as well as an increase in home working. The former are predominantly located in Pattenden Lane and more recently converted agricultural holdings throughout the parish. There is a broad range of companies, and local businesses are represented by a business forum that is active in supporting this sector of the village community. The economic health of the village is important and contributes to the overall wellbeing of its residents.

The Marden Neighbourhood Plan recognises the importance of sustaining a vibrant business economy and seeks to promote business interests where compatible with other policies in the plan. This accords with the aims of the NPPF that seeks to enable the sustainable growth and expansion of rural businesses, the development and diversification of agriculture and other rural businesses and enable sustainable rural tourism and leisure that respects the character of the countryside.

The MBC Local Plan has identified two areas of additional employment land to the east and west of the existing commercial/ industrial estate on Pattenden Lane – known as land south of Claygate and land west of Wheelbarrow Industrial Estate. The MBC Local Plan seeks to retain the existing industrial areas and prioritise the reuse of existing rural buildings for commercial rather than residential use.

Marden Neighbourhood Plan members have attended local business networking meetings to gauge the needs and aspirations of the existing business community. It is understood that businesses in Marden have a desire for commercial freehold and see the role of the Pattenden Lane Industrial Estate in providing smaller units as key in allowing space for 'start up' businesses.

The active business community makes Marden an attractive location, and Marden was described by one major employer as providing 'good value' in terms of rental costs. The move away from the traditional storage and distribution uses is inevitable considering the poor road transport links to the parish. Several manufacturing businesses have also sought to relocate away from the parish, with the need to be closer to major road links being cited as the motivator. However, it is essential to the overall life of the village that new commercial operations are attracted to Marden.

The MBC Local Plan seeks to ensure that businesses in the existing Pattenden Lane industrial estate continue to provide employment opportunities. This MBC policy promotes light industrial, general industrial, storage and warehousing uses. This is acknowledged; however, the policy also states that a change of use to any other non-industrial use, in total or in part, will only be permitted if it can be demonstrated that there is no reasonable prospect of an industrial use, or if an element of non-industrial use would more effectively meet the needs of modern business.

MBC's Economic Development Strategy 2015-2031 recognises the importance of manufacturing in the Borough, citing Marden as a focus for growth in



manufacturing, and sees the importance of securing the future of existing businesses as the best way of achieving economic growth.

The Marden Neighbourhood Plan seeks to support existing businesses but understands the limits of the location in terms of road transport links and thus also seeks to support the increasing number of 'innovative' companies that have begun to locate in the parish. It may, therefore, become necessary to consider a move away from class B1 (light industrial), B2 (general industrial) and B8 (storage and distribution) by supporting other types of mixed use that may include an element of retail, leisure or hi-tech use. However, the suitability of such uses will need to be considered on a site-by-site basis.

As noted Marden is attracting a wider range of commercial uses whose contribution to the parish's economic health should not be under-estimated. By way of example, Marden is proud to be home to an artisan gin manufacturer who uses local produce, a local cider producer who uses only Kentish apples; a brewery making traditional real ales and a vineyard using grapes grown in the parish. As a consequence, the Marden Neighbourhood Plan seeks to encourage less conventional business users and thus encourages greater flexibility in terms of use.

It is important to ensure that potential new businesses in Marden are not deterred by any uncertainty created by over-restrictive planning policies.

The Marden Business Forum has hosted events to showcase the existing businesses to the wider village. The Marden Neighbourhood Plan encourages such events which develop links designed to integrate the businesses community with the village, allowing residents to understand and be proud of its successful business community.

POLICY E1 – BUSINESS AND EMPLOYMENT

Support will be given to employment-generating businesses that maximise employment opportunities within the parish. Support will be given to development which provides opportunities for start-up ventures and contributes to the growing reputation of the parish as a location for innovative commercial uses and those with a local connection or using local produce. The development should have suitable road access to and from primary routes such as the A229 and should not result in any unacceptable impact on residential amenity or the character of the surrounding area and wider countryside. The development should be suitably landscaped to reflect Marden's rural setting.

It is noted that the westernmost part of the Pattenden Lane industrial/commercial area is shown on the MBC Local Plan map for Policy SP9 (Marden Rural Service Centre) within the settlement boundary but not as part of the economic development area. However, this small triangular plot has been used for light industrial/vehicle repair purposes for many years and would not be suitable for residential development.

It is also noted that the majority of the large Claygate distribution warehouse site, granted planning permission in 2007, is shown as being located outside

both the settlement boundary and the economic development area. However, the reality is that it is now part of the wider Pattenden Lane commercial estate and is neither open countryside nor suitable for residential development.

Further action required

- ▶ For clarity, MBC to modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) at the next periodic review to encompass the light industrial/vehicle repair site at the westernmost part of the Pattenden Lane industrial/commercial area within the economic development area – refer to area FA2 on the ‘Planning Policies & Further Actions’ map.
- ▶ For clarity, MBC to modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) at the next periodic review to encompass the whole of the Claygate distribution warehouse site within the settlement boundary – refer to area FA3 on the ‘Planning Policies & Further Actions’ map.
- ▶ Similarly, MBC to modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) at the next periodic review to encompass the whole of the Claygate distribution warehouse site within the economic development area – refer to area FA4 on the ‘Planning Policies & Further Actions’ map.

Retail



Marden, like many other villages, has a variety of shops, pubs and other services. At its peak, there were a selection of 22 retail premises but there has been a gradual diminution over the years. However, Marden is a designated Rural Service Centre and it is therefore important that the widest range of shops and services are provided. This is essential as the population of the parish increases over the life of the plan to ensure development is truly sustainable and to promote the social interactions that contributes to Marden’s cohesion.

The MBC Local Plan highlights the High Street and junction with Maidstone Road as a district centre. However, Church Green also has an important retail function with a butcher’s shop, convenience store, fish and chip shop, hairdressers, garage and dental surgery. This area has therefore been included in the Marden Neighbourhood Plan as a district centre.

There are also other retailers and service providers located outside these local district centres –Stanley’s garage, West End Stores, West End Tavern public house, The Village Club, Marden Tandoori and the Stilebridge public house – which are central to village life and the role of Marden as a Rural Service Centre. Consequently the loss of such established businesses would be strongly resisted.

The plan recognises that shopping habits are changing rapidly. Therefore the retailers seeking to locate in Marden are likely to be service providers. This may also generate the need for shops and services to locate outside the recognised district centres. The plan seeks to be sufficiently flexible to accommodate future market trends.

POLICY E2 – RETAIL - Eat, meet and greet

Support will be given to the creation, retention and enhancement of shops and other uses that service the community of Marden.

Further action required

- ▶ For clarity, MBC to modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) at the next periodic review to designate an additional local district centre at Church Green (refer to area FA5 on the 'Planning Policies & Further Actions' map).
- ▶ MBC to modify the map for Local Plan Policy SP9 to extend to the south east and to include the Village Club, Stanleys Garage and Marden Tandoori. (Refer to area FA6 on the Planning Policies and Further Action Map.).

The consultation process has identified the following types of shops and other 'day-to-day' services that would be of benefit to the Parish:

Café or bistro	Florist
Optician	Funeral Directors
Clothing shop	Bank
Craft shop	Small scale horticultural retailer
Ironmongers	Bakery
Pet shop	Cookshop

Business Signage



Many of Marden's shops and businesses are located within the Conservation Area meaning the design of their shop frontages and advertising signage can have a significant impact on the visual appearance of the village. It is to be regretted that many of the traditional shop fronts have been replaced with large modern glazed panels that have had a detrimental impact on the character of the building and the wider area. It is therefore important to retain those existing frontages that have remained, for example, John's barbers and the Green Door. It is also desirable to encourage the reinstatement of traditional shop frontages. Whilst the re-creation of a bygone age may be unachievable or even undesirable, it may be possible to reinstate the appropriate window proportions.

Poorly designed advertising signage can have an adverse impact on the character of the building and the wider area, particularly when sited within the Conservation Area, adjacent to listed buildings or in the countryside. The needs of the occupier to promote their goods and services are recognised, so a balance between economic need and visual amenity needs to be recognised.

POLICY E3 – BUSINESS SIGNAGE

The scale, position, materials and colour of business signs must be designed to minimise any detrimental impact on the character and appearance of the building and the surrounding area, including the Conservation Area. Where appropriate signs should be designed to reflect the original proportions and style of the building. Illuminated signs will be supported if illumination is deemed to be essential to the operation of the business, the levels of illumination are kept to the necessary minimum and only operated during opening hours.

Developer Contributions



What does the future hold for Marden?



Developer contributions, 'planning obligations' or 'planning gain' are the financial benefits that may be gained from a development proposal. Where required, a developer will make a financial contribution to compensate for the increased demand on the existing infrastructure as a result of the development. These contributions can be made through legal planning agreements under Section 106 of the Town and Country Planning Act 1990 (often known as 'S106 contribution') and relate to a specific development. The contributions can also be sought through the Community Infrastructure Levy (CIL), which is a financial contribution charged at a standard rate. MBC approved the Community Infrastructure Levy charging schedule effective from October 2018.

The NPPF recognises the importance of developer contributions and makes specific reference to financial contributions towards affordable housing provision. However, planning obligations can only be sought when they are necessary to make the development acceptable in planning terms, directly relate to the development and are fair and reasonable in scale.

The MBC Local Plan states that developers will be expected to provide or contribute towards the additional requirements generated by a development. The policy recognises that there will be many competing demands and has a set of common priorities that apply across the borough.

The Marden Neighbourhood Plan recognises the importance that these contributions can make to Marden, and it is thus essential to maximise any benefits from developments within the parish. To do this it is vital for developers, planners and MBC Planning Department to understand the needs of the parish in order to direct any monies that may be forthcoming to where they are really needed.

Marden Parish Council has produced a working policy document relating to developer contributions. (Marden Parish Council Infrastructure Spend Plan). This document identifies areas which the parish sees as local priorities. Residents were asked to comment on these areas at the 2013 and 2014 Marden Neighbourhood Plan Open Days and the policy is reviewed and updated regularly by the Parish Council. Each update is shared with MBC, and the document is available to all.

An unprecedented number of new homes have been permitted in Marden since 2013. The anticipated 573 new dwellings are either already completed or under construction. The Marden Neighbourhood Plan does not seek to prevent development and recognises the many advantages that development can bring to a community. However, given the size of the expansion, which represents a 37% increase in the number of dwellings, it is not surprising that residents have concerns about the cumulative impact of such large scale developments over such a short timescale. [2011 Census of Population 1542 households in the Parish: source NOMIS]

The delays in the production of the MBC Local Plan led to a shortfall in the five year housing supply required under the NPPF. This borough wide shortfall

allowed for new development over which local people had little control. This situation must not be allowed to reoccur. The intention is, therefore, to reassess the Marden Neighbourhood Plan on a regular basis as the village must be given time to assimilate the already permitted development before any further development sites can realistically be considered.

What does the future hold for the Marden Neighbourhood Plan?

The Neighbourhood Plan will need to be reviewed and updated at regular intervals together with a review of the allocation of land for development. Marden Parish Council and the Marden Neighbourhood Plan Steering Group will work with MBC during the planned MBC Local Plan review to be completed in 2021 and adopted by 2022.

Without pre-judging what may be decided at that time, some of the issues that have been raised by residents are:

- ▶ Future housing land allocations should consider whether developments should be permitted wholly or partially located north of the railway line or in outlying settlements such as Chainhurst. Due to the large scale development that has been built since 2013 it is the view of Marden Neighbourhood Plan that any future development permitted until 2031 should not increase the size of the village beyond 50% of the 2011 number of dwellings, ie an additional 198 dwellings.
- ▶ Economic development land allocations in order to ensure that local employment opportunities grow in parallel with residential development.
- ▶ Allocation of land for any facilities which may have outgrown their existing sites, or where the existing buildings may have reached the end of their useful life (in particular the school, memorial hall, medical centre, etc.).
- ▶ Allocation of land for new youth facilities.
- ▶ Allocation of land for additional station parking.

Spatial Application of Policies

Map at Annex 1

Natural Environment		Spatial Application		Page No
Water Management	NE1	Surface Water Management	Whole Parish	11
Water Quality	NE2	Water Quality	Whole Parish	12
Sense of Place	NE3	Landscape Integration	Whole Parish	14
Habitat Conservation	NE4	Biodiversity and Habitats	Whole Parish	16
	NE5	Landscape Planting	Whole Parish	17
Soil Conservation	NE6	Soil Conservation	Whole Parish	18
Built Environment				
Local Character	BE1	Local Character	Whole Parish	19
Residential Amenity	BE2	Residential Amenity	Whole Parish	20
Sustainable Construction	BE3	Sustainable Construction	Whole Parish	23
Rural Buildings	BE4	Conversion of Rural Buildings	Whole Parish	24
Farm Buildings	BE5	New Farm Buildings	Outside settlement boundary	25
	BE6	Seasonal Worker Accommodation	Outside settlement boundary	25
Amenities				
Community Facilities	A1	Community Facilities	Whole Parish	27
Open Spaces	A2	Open Space	Whole Parish	28
Education	A3	Primary Education	Marden Primary School	30
Healthcare	A4	Healthcare Facilities	Whole parish	31
Infrastructure				
Water Supply and Sewerage	In1	Water Supply/ Water Supply and Sewerage	Whole parish	32
Transport	In2	Sustainable Travel	Whole Parish	35
	In3	Additional Traffic	Whole Parish	35
	In4	Station	Marden Station	35
Housing	In5	Affordable Housing	Whole Parish	37
	In6	Housing for Older People	Whole Parish	38
	In7	Housing for Gypsies and Travellers	Whole Parish	39
Economy				
Business and Employment	E1	Business and Employment	Whole Parish	41
Retail	E2	Retail - eat, meet and greet	Whole Parish	42
Business Signage	E3	Business Signage	Whole Parish	43

Planning Policies and Further Actions Map

(includes the Conservation Area of Marden)

KEY: (also refer to previous list of MNP Policies)

Employment

- EMP1(2) MBC Policy for South of Claygate, Pattenden Lane, Marden
- EMP1(3) MBC Policy for West of Wheelbarrow Industrial Estate, Pattenden Lane, Marden

Further Actions


- FA1 MNP Housing Further Action
- FA2 MNP Policy E1 Further Action
- FA3 MNP Policy E1 Further Action
- FA4 MNP Policy E1 Further Action
- FA5 MNP Policy E2 Further Action
- FA6 MNP Policy E2 Further Action

Housing

- H1(43) MBC Policy for Howland Road, Marden
- H1(44) MBC Policy for Stanley Farm, Plain Road, Marden
- H1(45) MBC Policy for The Parsonage, Goudhurst Road, Marden
- H1(46) MBC Policy for Marden Cricket and Hockey Club, Stanley Road, Marden
- H1(47) MBC Policy for South of The Parsonage (Vicarage Field), Goudhurst Road, Marden

Open Spaces

- OS(8) MBC Policy for The Parsonage, Goudhurst Road, Marden (2.16ha)



- LEGEND**
- MBC Conservation Area
 - MNP further actions
 - MNP policies
 - MBC economic development area
 - MBC open space allocation
 - MBC employment allocation
 - MBC housing allocation
 - MBC local retail centre
 - MBC settlement boundary
 - MBC policy numbers
 - Marden Parish Boundary

**Marden
Neighbourhood Plan**

Planning Policies and Further Actions

SCALE : 1 : 6485 @ A4 DATE : 11/04/2019

MAP FILENAME : MNP Planning Policies & Future Action Map April 2019


N


Map data shown may contain Ordnance Survey products supplied by Pear Technology Services Ltd. Email: info@peartechnology.co.uk
 © Crown Copyright and database rights from date shown above
 Ordnance Survey licence number 100023148

List of Further Actions and Owners










<i>Page</i>	<i>Owner</i>	<i>Action</i>
11	All partners	Take forward recommendations of KCC's Marden Surface Water Plan 2017 and revisions.
11	Environment Agency	To confirm whether all or part of Marden should be designated a Critical Drainage Area.
11	All land owners	With riparian responsibilities to ensure existing ditches are fit for purpose and maintained as such.
12	All partners	To take forward recommendations of the Beult and Teise Catchment Improvement Groups.
19	Marden Parish Council	To lobby MBC to undertake a Conservation Area Appraisal and Management Plan for Marden.
27	KCC; Marden Parish Council; Marden History Group	To continue working together to secure the future of the Marden Library and Heritage Centre.
27	KCC and Marden Parish Council	To continue working to ensure youth facilities are provided in the Parish.
30	Marden Parish Council	To continue to lobby KCC about subsidised travel arrangements to secondary schools attended by Marden children.
30	KCC	To ensure that existing S106/future CIL developer contributions are used proportionately to support the provision of secondary school education for Marden children.
30	Marden Parish Council	To explore possible provision for nursery care and education within the parish of Marden to provide good quality facilities for pre-school children.
35	Station infrastructure stakeholders - Network Rail, train operating company, Dept of Transport, KCC and Marden Parish Council	To pursue enhancement opportunities including additional station parking and step free access to the 'down' platform.
35	Bus infrastructure stakeholders - bus operating companies, KCC, MBC, Marden Parish Council	To pursue enhancement opportunities including additional bus services, new or replacement bus stop signage, road markings and bus shelters.
36	MBC	To modify the map for Local Plan SP9 (Marden Rural Service Centre) at the next periodic review to encompass the major Highwood Green housing development given planning permission in 2012 and completed in 2017 within the settlement boundary.

<i>Page</i>	<i>Owner</i>	<i>Action</i>
36	Marden Parish Council and Marden Neighbourhood Plan Steering Group.	To monitor progress and keep residents informed of the 2019 'call for sites' exercise.
39	Marden Parish Council and Marden Neighbourhood Plan Steering Group.	To monitor the distribution of planning permission for new gypsy and traveller sites across the borough.
42	MBC	To modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) to encompass the light industrial/vehicle repair site at the western most part of the Pattenden Lane industrial/commercial area within the economic development area.
42	MBC	To modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) to encompass the whole of the Claygate distribution warehouse site within the settlement boundary.
42	MBC	To modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) to encompass the whole of the Claygate distribution warehouse site within the economic development boundary.
43	MBC	To modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) to designate an additional local district centre at Church Green.
43	MBC	To modify the map for Local Plan Policy SP9 (Marden Rural Service Centre) to extend to the south east and to include the Village Club, Stanleys Garage and Marden Tandoori.







Flood Maps

- | | | |
|---|---|---|
|  Floodzone 2 |  Floodzone 3 |  Historic Flood Map |
|  Recorded Flood Outlines |  Risk of Flooding High |  Risk of Flooding Medium |
|  Risk of Flooding Low |  Risk of Flooding Very Low | |
|  Marden Parish Boundary | | |

Ancient Woodland and SSSIs Map





Marden Neighbourhood Plan Ancient Woodland and SSSI

SCALE : 1 : 5000 @ A3 DATE : 18/04/2019

MAP FILENAME : Map MNHP 2019 SSSI and Ancient woodland

Map data shown may contain Ordnance Survey © products supplied by Pear Technology Services Ltd; Email: info@peartechology.co.uk © Crown Copyright and database rights from date shown above Ordnance Survey © licence number 100023148



Listed Buildings (taken from Historic England Website September 2018)

ALBION ROAD		List Entry No	Heritage Category
1	MONKTON HOUSE	1060704	Grade: II
2	PUMP ABOUT 10 METRES WEST OF ALLENS	1060705	Grade: II
3	ALBION HOUSE	1060706	Grade: II
4	BISHOP HOUSE / JEWELL HOUSE (2 properties)	1060707	Grade: II
5	WORKING MENS CLUB (now Village Club)	1060703	Grade: II
BATTLE LANE			
6	BLUE HOUSE COTTAGE	1045872	Grade: II
7	BARN ABOUT 10 METRES WEST OF WANSHURST	1060708	Grade: II
8	1 & 2 BLUE HOUSE COTTAGES (2 properties)	1060710	Grade: II
9	SHARPS (St Anne's Green Lane)	1060711	Grade: II
10	WHITE COTTAGE	1344391	Grade: II
11	WANSHURST GREEN FARMHOUSE	1344392	Grade: II
12.	BARN ABOUT 25 METRES SOUTH WEST OF VERRELLS COTTAGE SHARPS (St Anne's Green Lane)	1344393	Grade: II
13	LITTLE WANSHURST	1344411	Grade: II
14.	BARN ABOUT 15 METRES EAST OF SUMMERHILL HOUSE	1045847	Grade: II
15.	OASTHOUSE ABOUT 30 METRES NORTH WEST OF MANOR FARMHOUSE (NOW Manor Farm Oast)	1344412	Grade: II
16.	WANSHURST	1060709	Grade: II
17.	OASTHOUSE ABOUT 15 METRES NORTH NORTH EAST OF SUMMERHILL HOUSE	1060712	Grade: II
18.	MANOR FARMHOUSE	1060673	Grade: II
19.	BARN ABOUT 40 METRES SOUTH SOUTH WEST OF MANOR FARMHOUSE	1060674	Grade: II
20.	REEVES COTTAGE	1060675	Grade: II
21.	SUMMERHILL HOUSE	1045834	Grade: II
22.	MILE BUSH FARMHOUSE (formerly listed as Horlands Farm)	1045879	Grade: II
CHURCH GREEN			
23.	CHURCH GREEN HOUSE	1054780	Grade: II
24.	1 & 2 CHURCH GREEN COTTAGES (2 properties -Pattenden Lane)	1203232	Grade: II
DAIRY LANE			
25.	TITHE BARN	1060682	Grade: II
26.	REED PLACE FARMHOUSE (Now split into cottages?)	1055863	Grade: II
27.	BARN ABOUT 50 METRES NORTH WEST OF OLD TIMBERS	1055875	Grade: II
GOUDHURST ROAD			
28.	SPRINGFIELD FARMHOUSE	1060683	Grade: II
29.	GREAT CHEVENY HOUSE & GREAT CHEVENY HOUSE SOUTH (2 properties)	1055805	Grade: II*
30.	GREAT CHEVENY (formerly listed as Cheveney Farm House)	1060685	Grade: II

GOUDHURST ROAD (continued)		List Entry No	Heritage Category
31.	BARN ABOUT 15 METRES NORTH OF LOVES FARMHOUSE (<i>Now Oakstream Barn</i>)	1366598	Grade: II
32.	BARN ABOUT 30 METRES NORTH WEST OF GREAT CHEVENY HOUSE	1344418	Grade: II
33.	TURKEY FARM HOUSE	1060684	Grade: II
34.	OASTHOUSE ABOUT 30 METRES WEST OF TANNER HOUSE	1366622	Grade: II
35.	TANNER HOUSE	1366631	Grade: II
36.	BARN ABOUT 30 METRES NORTH WEST OF TANNER HOUSE	1344419	Grade: II
37.	BARN ABOUT 30 METRES WEST OF GREAT CHEVENY HOUSE	1055818	Grade: II
38.	BEALE FARM HOUSE	1055824	Grade: II
39.	OASTHOUSE ABOUT 6 METRES NORTH OF SPRINGFIELD FARMHOUSE	1055847	Grade: II
40.	BREWHOUSE ABOUT 6 METRES EAST OF SOUTH END OF GREAT CHEVENY HOUSE	1060686	Grade: II
41.	FORMER STABLES ABOUT 20 METRES SOUTH WEST OF GREAT CHEVENY HOUSE	1060687	Grade: II
42.	LOVES FARMHOUSE	1060688	Grade: II

HIGH STREET

43.	CHURCH OF ST MICHAEL AND ALL ANGELS	1054804	Grade: I
44.	STOCKS ABOUT 1/2 METRE SOUTH OF SOUTH AISLE OF CHURCH OF ST MICHAEL AND ALL ANGELS	1344417	Grade: II
45.	MARDEN FARM SHOP (<i>formerly listed as Court House/The Old Market House</i>)	1038292	Grade: II
46.	WHITE LYON HOUSE	1345537	Grade: II*
47.	MILESTONE ADJACENT TO EAST ELEVATION OF WHITE LYON HOUSE	1060691	Grade: II
48.	SHEPHERD'S HOUSE	1060690	Grade: II
49.	RAILINGS ABOUT 3 METRES EAST OF SHEPHERD'S HOUSE	1344420	Grade: II
50.	RAILINGS ABOUT 3 METRES SOUTH AND EAST OF SHEPHERD'S HOUSE	1345571	Grade: II
51.	WARD AND PARTNERS (<i>formerly listed as J.H Sutton, Agricultural Merchants</i>) (<i>now The Rowans</i>)	1060654	Grade: II
52.	TURNPIKE HOUSE (<i>formerly listed as J.A. Castleton Butchers and house attached</i>)	1374152	Grade: II
53.	BANK HOUSE, BRIDGELANDS COTTAGE, GREENHAYS COTTAGE AND NATIONAL WESTMINSTER BANK (4 properties) (<i>formerly listed as The National Provincial Bank Ltd</i>)	1060655	Grade: II
54.	VINE HOUSE (<i>formerly listed as The House attached to J H Sutton, Agricultural Merchants</i>)	1344441	Grade: II
55.	JH SUTTON AND SON LIMITED AND HOUSE TO RIGHT (2 properties) (<i>now The Old Seed Shop and Shipton Cottage</i>)	1344404	Grade: II
56.	OLD CHURCH COTTAGE	1055737	Grade: II
57.	JOHN'S HAIRDRESSER, MARSIDA, VICKY CLARK (<i>now The Old Sweet Shop - 3 properties</i>)	1060658	Grade: II
58.	EW BEALE (CHEMISTS) G FELTHAM, BUTCHER NATIONAL FARMERS' UNION OFFICE (3 properties) (<i>now Marden Chemist, Munchies Bakers and The Green Door</i>)	1344405	Grade: II
59.	THE COTTAGE	1344403	Grade: II
60.	THE BRIDGE HOUSE	1060656	Grade: II
61.	FORMER STABLES ABOUT 60 METRES SOUTH EAST OF THE BRIDGE HOUSE) (<i>now The Old Stables</i>)	1060657	Grade: II
62.	OASTHOUSE ABOUT 180 METRES SOUTH WEST OF EW BEALE (CHEMISTS) LIMITED (<i>now Sutton Forge Oast, Sutton Forge</i>)	1060659	Grade: II
63.	THE PLACE (<i>formerly listed as The House attached to Hayes Grocers</i>) (<i>now Briars Cottage</i>)	1060692	Grade: II

HOWLAND ROAD		List Entry No	Heritage Category
64.	STONE PIT FARMHOUSE	1031808	Grade: II
65.	MOTE COTTAGE	1031814	Grade: II
66.	AMHURST COTTAGES (2 properties) (now Poacher's Keep and Pastures End)	1060661	Grade: II
67.	BARN ABOUT 20 METRES NORTH WEST OF STONE PIT FARMHOUSE	1060662	Grade: II
68.	VINE COTTAGE AND YEOMAN COTTAGE (2 properties):	1344406	Grade: II
69.	THE OLD HOUSE	1376660	Grade: II
70.	BRIDGEHURST FARMHOUSE	1352657	Grade: II
71.	1 & 2 JEWEL COTTAGES (2 properties)	1060660	Grade: II

HUNTON ROAD

72.	FORMER STABLES ABOUT 23 METRES SOUTH EAST OF ORCHARD DENE	1031794	Grade: II
73.	MILL FARMHOUSE (formerly listed as Marden Mill)	1031387	Grade: II
74.	BARN ABOUT 20 METRES SOUTH WEST OF MILL FARMHOUSE	1344407	Grade: II
75.	MURZIE FARMHOUSE	1344408	Grade: II
76.	CHAINHURST FARMHOUSE	1060663	Grade: II*
77.	GATEHOUSE FARMHOUSE	1060666	Grade: II
78.	NEW LODGE HOUSE (formerly listed as New Lodge)	1060667	Grade: II
79.	FORMER BARN ABOUT 30 METRES NORTH NORTH WEST OF CHAINHURST FARMHOUSE	1376655	Grade: II
80.	BARN ABOUT 40 METRES NORTH WEST CHAINHURST FARMHOUSE	1060664	Grade: II
81.	OASTHOUSE ABOUT 40 METRES WEST OF GATEHOUSE FARMHOUSE	1060668	Grade: II
82.	BARN ABOUT 70 METRES NORTH NORTH WEST OF GATEHOUSE FARMHOUSE	1060665	Grade: II
83.	BARN ABOUT 3 METRES NORTH WEST OF MURZIE FARMHOUSE	1025895	Grade: II
84.	BARN ABOUT 15 METRES WEST SOUTH WEST OF NEW LODGE HOUSE (now New Lodge Barn)	1031338	Grade: II
85.	BARN ABOUT 25 METRES SOUTH EAST OF REED COURT	1031361	Grade: I

MAIDSTONE ROAD

86.	OASTHOUSE ABOUT 15 METRES SOUTH OF STILEBRIDGE FARMHOUSE	1025304	Grade: II
87.	OASTHOUSE ABOUT 3 METRES EAST OF CHURCH FARM HOUSE	1025875	Grade: II
88.	STILEBRIDGE FARMHOUSE	1344409	Grade: II
89.	ROSE'S SHOP (now 1 High Street) SMEETON (now Smeeton, 2 High Street) AND THE WOODSTOVE TRADING COMPANY (now 1 Culpeppers & 2 Maidstone Road) (3 properties)	1344421	Grade: II
90.	CORNERWAYS (formerly listed as The Farm Shop)	1057687	Grade: II
91.	CHURCH FARM HOUSE	1060669	Grade: II
92.	THE OLD VICARAGE	1060670	Grade: II

PARK ROAD

93.	MOUNTAIN FARMHOUSE	1025309	Grade: II
94.	BARN ABOUT 15 METRES WEST OF MOUNTAIN FARMHOUSE (now Mountain Barn)	1344410	Grade: II
95.	NASH COTTAGE (Wilden Park Road)	1203220	Grade: II
96.	SUSANS FARM (Wilden Park Road)	1060671	Grade: II

PLAIN ROAD

97.	POULTERS HALL	1060672	Grade: II
-----	---------------	---------	-----------

SHEEPHURST LANE (formerly listed as BEECH ROAD)		List Entry No	Heritage Category
98.	BLACKMOOR FARMHOUSE	1060678	Grade: II
99.	BARN ABOUT 150 METRES SOUTH OF BEECH FARMHOUSE (now <i>Beech Barn</i>)	1344416	Grade: II
100.	CORNWELLS	1367062	Grade: II
101.	BEECH FARMHOUSE	1054841	Grade: II
102.	OAST HOUSE AT BEECH FARM	1262042	Grade: II
103.	BEECHIN HOUSE	1344413	Grade: II
104.	WILLOWS	1054874	Grade: II
105.	BARN ABOUT 26 METRES NORTH OF BLACKMOOR FARMHOUSE	1060679	Grade: II
SHERENDEN LANE			
106.	SHERENDEN FARMHOUSE	1281775	Grade: II
STAPLEHURST ROAD			
107.	OLD HERTSFIELD FARMHOUSE	1281781	Grade: II
108.	HOME FARMHOUSE	1203265	Grade: II
109.	BARN ABOUT 50 METRES EAST OF OLD HERSTFIELD FARMHOUSE (now <i>Hertsfield Barn</i>)	1344432	Grade: II
110.	STILEBRIDGE COTTAGE	1060633	Grade: II
STILEBRIDGE LANE			
111.	LITTLE TILDEN FARMHOUSE	1060634	Grade: II
SUMMERHILL ROAD			
112.	LITTLE HICKMOTTS	1203272	Grade: II
THORN ROAD			
113.	LONGRIDGE	1060635	Grade: II
114.	THORN COTTAGE (formerly listed as <i>Thorn Farm Cottage</i>)	1344433	Grade: II
115.	THORN FARMHOUSE	1060642	Grade: II
116.	ASHLEY HOUSE	1203278	Grade: II
TILDEN LANE			
117.	GREAT TILDEN FARMHOUSE	1060636	Grade: II
118.	THE BARN (formerly listed as <i>Barn at Great Tilden</i>)	1344434	Grade: II
119.	FORMER GRANARY ABOUT 3 METRES NORTH OF GREAT TILDEN FARMHOUSE (now <i>The Oast</i>)	1203294	Grade: ii
UNDERLYN LANE			
120.	COPT HALL FARMHOUSE	1060637	Grade: II
121.	CHAMBERS COTTAGES AND UNDERLYN FARM COTTAGES (3 properties) (formerly listed as <i>The White House, Underlyn Lane</i>) (Now 1, 2 and 3 Chambers Cottages)	1203308	Grade: II
122.	OASTHOUSE ABOUT 40 METRES SOUTH OF NOS 5 AND 6 LITTLE MILL COTTAGES	1203330	Grade: II
123.	5 & 6 LITTLE MILL COTTAGES (2 properties)	1060638	Grade: II
124.	TARGET FARMHOUSE	1203320	Grade: II

WEST END	List Entry No	Heritage Category
125. AMBER COTTAGE AND FERN COTTAGE (<i>2 properties</i>)	1281741	Grade: II
126. THE WENTWAYS	1060639	Grade: II
127. WESTFIELD (<i>Goudhurst Road</i>)	1060641	Grade: II
128. THE LIMES, THE MANSE AND HOUSE ATTACHED TO CONGREGATIONAL CHURCH (<i>3 properties</i>)	1060640	Grade: II
129. 1, 2, 3 & 4 WEST END COTTAGES (<i>row of cottages</i>)	1203365	Grade: II

Acknowledgements

The Marden Neighbourhood Plan Steering Group would like to acknowledge the help and support of all those who have contributed to the production of the plan.

All photographs and images contained in this report remain the property of the Marden Neighbourhood Plan Steering Group.

